



2297 Highway 12,
PO Box 130
Breachin, Ontario L0K 1B0
p.705-484-5374
f. 705-484-0441

Development and Infrastructure Department
Contract # ID-08-2025
2025 Hot Mix Asphalt Surface Treatment
Addendum No. 1

Issue Date: September 26, 2025

Questions/Answers

Q1: Can the Township please confirm if a bid security is required. There is no mention in the RFT with the exception of the bid form requesting that we enter a dollar figure for a certified cheque.

A1: There is no requirement of a bid security (see page 7, Tender Deposit). Please indicate N/A on the Tender Summary document. For further clarification, submissions without a certified cheque will be deemed compliant and acceptable for the purposes of this section.

Q2: With respect to McRae Park Road; upon a site review, it was noted that asphalt gutters exist. Will the contractor be required to reinstate these gutters? And if so, how will the contractor be compensated for this.

A2: Yes, the contractor will be responsible for the removal and reinstatement of the gutters, where they are currently located. Please see the amendments listed below as the pricing schedule is to be replaced and include the pricing for the gutters. Gutters will be paid by linear meter.

Q3: Is it possible for the Township to provide the shouldering quantity so that all contractors submitting pricing will be doing so on the same scope of work to ensure there is no bid upset?

A3: Yes, please see the updated below updated pricing schedule. The successful bidder will still be responsible for confirming quantities in the field. The values indicated are estimates only.

Amendments

1. All bidders are hereby to remove and replace "Schedule I – Items and Prices" with the following pages. Any bids received with the incorrect Schedule I shall be deemed non-compliant and will not be accepted.

SCHEDULE I – ITEMS AND PRICES

Any modifications of this form will result in the bid being disqualified. This Bid Form must be completed in full.

1. McRae Park Road: Glencoe Beach Road to just past Hilltop Road (Park Entrance) at Road End

ITEM	SPEC #	DESCRIPTION	UNIT	Est. QUANTITY	UNIT PRICE	AMOUNT BID
1.1	510	Mill and remove existing asphalt to a depth of 120 mm	Sq. m	10,220		
1.2	206	Fine grading and compaction of pulverized road surfaces prior to paving	Sq. m	10,220		
1.3	310	HL8 asphalt surfacing supply and place 60 mm to achieve a 2% cross fall	Sq. m	10,220		
1.4	310	HL3 asphalt surfacing supply and place 60 mm to achieve a 2% crossfall	Sq. m	10,220		
1.5	308	Tack coat	Sq. m	10,220		
1.6	314	Shouldering with granular A between 0 – 1 m wide shoulder to match existing width and grade	Linear m	2,800		
1.7	312	HL3 asphalt gutter to be reinstated, where applicable, 0.45 m in width	Linear m	120		
1.8	Traffic Control	Only single lane closures will be permitted	Lump Sum			
1.9		Driveway repaving / restoration / tie-ins (All)	Lump Sum			

TOTAL: "A" McRae Park Road: Glencoe Beach Road to just past Hilltop Road

\$ _____

Initials: _____ Date: _____

2. Glencoe Beach Road: McRae Park Road to End

ITEM	SPEC #	DESCRIPTION	UNIT	Est. QUANTITY	UNIT PRICE	AMOUNT BID
2.1	206 / 314 / 501	Supply / grading / compaction of base material (including gravel estimated tonnage).	Lump sum	2,800m ²		
2.2	310	HL3 asphalt surfacing supply and placement of 50mm to achieve 2% crossfall.	Sq. m	2,800m ²		
2.3	314	Shouldering with granular A to a minimum of 0.5 m wide to match existing width and grade.	Linear m			
2.4	310	Driveway repaving / restoration / tie-ins (All)	Lump sum			

TOTAL: "B" Glencoe Beach Road: McRae Park Road to End

\$ _____

Initials: _____ Date: _____

The Corporation of the Township of Ramara reserves the right to accept or reject all or part of any Bid and reserves the right to accept other than the lowest Bid and to cancel this Call for Bid at any time.